# City Council Workshop – August 21, 2023







# **Project Description**

- Construct a Pedestrian Connection Between Winnipesaukee River Trail and Mill City Park
- Awarded a Grant from NHDOT in 2019
  - NHDOT Funding \$512,000
  - City Funding \$128,000
  - Total Funding \$640,000
  - (Assumed Replacing Railroad Ties with Solid Timber Deck)
  - Project Must Follow NHDOT Prescribed Process





# Description of Bridge

- Built circa 1890's
- 15-Spans, 356' Long, 12' Wide, 20' Above Ground
- 3 Types of Trestle Spans
  - 1. Standard (Spans 1-6 & 15)
  - 2. A-Frame (Spans 8-13)
  - 3. Inverted King Post (Spans 7 & 14)









### 2019 Inspections Results

#### **Condition Summary Table**

Element	Total	Green (Retain)	%	Red (Replace)	%	Yellow (Repair)	%
Bents	70	27	39%	20	29%	23	33%
Stringers	90	10	11%	38	42%	42	47%
A-Frames	30	12	40%	8	27%	10	33%
	190	49	26%	66	35%	75	39%





# Structural Inspection Findings

- Portions of the Truss are in Poor Condition
- Truss is Continuing to Deteriorate
- 2019 Inspection Led to Path Relocation







## Current Alternatives

- Rehabilitate Existing Railroad Trestle
  - Remove Rail, Ties, & Stringer and Put on New Deck & Historic Style Railing
  - Rehabilitate and Replace Trestle Members In Kind
- New Railroad Trestle
  - Replicate Existing Design
  - All New Timber Members
- New Pedestrian Bridge Upstream
  - Includes Maintenance Work To Existing Trestle





## Current Alternatives

- Stabilize Trestle
  - Remove Vegetation
  - Repair or Replace Failed Trestle Members In Kind
  - Will Not Allow Pedestrian Traffic On Trestle

- Remove Trestle
  - Coordinate Stone Pier Removal





## Alternative Cost Estimates

	ALTERNATIVE COST ESTIMATES									
	HISTORIC RESTORATION ALTERNATIVES FOR PEDESTRIAN LOADING			NEW PEDESTRIAN BRIDGE &		NO-BUILD & STABILIZE		NO-BUILD &		
	R	EHABILITATE TRESTLE	REI	PLACE TRESTLE IN-KIND		STABILIZE TRESTLE	TRESTLE		REMOVE TRESTLE	
TIMBER TRESTLE WORK	\$	2,200,000	\$	1,925,000	\$	1,000,000	\$	1,000,000	\$	500,000
NEW CONCRETE RIVER PIERS (TBD)	\$	550,000	\$	550,000	\$	-	\$	-	\$	-
PEDESTRIAN DESIGN & HISTORIC STYLE RAILING	\$	625,000	\$	625,000	\$	-	\$	-	\$	-
CONTINGENCY	\$	350,000	\$	300,000	\$	225,000	\$	225,000	\$	100,000
MOBILIZATION	\$	350,000	\$	300,000	\$	225,000	\$	225,000	\$	100,000
NEW PEDESTRIAN BRIDGE & FOUNDATIONS	\$	-	\$	-	\$	1,495,000	\$	-	\$	-
APPROACH WORK	\$	75,000	\$	75,000	\$	60,000	\$	-	\$	-
TOTAL CONSTRUCTION COST ESTIMATE	\$	4,150,000	\$	3,775,000	\$	3,005,000	\$	1,450,000	\$	700,000
ENGINEERING, GEOTECHNICAL & PERMITTING	\$	375,000	\$	350,000	\$	240,000	\$	150,000	\$	50,000
CONSTRUCTION ENGINEERING (7% CONSTRUCTION)	\$	290,000	\$	260,000	\$	210,000	\$	100,000	\$	-
TOTAL PROJECT ESTIMATE		4,815,000	\$	4,385,000	\$	3,455,000	\$	1,700,000	\$	750,000
CITY SHARE		20%		20%		20%		100%		100%
CITY COST	\$	963,000	\$	877,000	\$	691,000	\$	1,700,000	\$	750,000
CITY COST	\$	963,000	\$	877,000	\$	691,000	\$	1,700,000	\$	750,000

\$640,000 Already Funded (\$512,000 DOT - \$128,000 City)





# New Railroad Trestle Alternatives

- Modern Materials Could Be Used to Build a More Efficient Trestle
  - Fewer Bents
  - Longer Spans
  - Would Change the Look of the Trestle
  - Would Lower Construction Costs
  - Require Additional Coordination with Resource Agencies
  - Wide Range of Options





# October 11, 2022 Meeting Summary

- Concerns with Rehab Option
  - Future Maintenance Costs
  - Unknows During Construction
- Not Much Support for New Bridge Upstream of Trestle
- New Trestle Preferred
  - Explore Options To Reduce Costs and Future Maintenance
  - Use of Modern Materials







## NHDOT Grant Requirements

- 1. Engineering Study
  - Develop A Range of Alternatives
  - Select Locally Preferred Alternative
  - Preliminary Design
    - Refine Locally Preferred Alternative
    - Fully Evaluate Impacts of Proposed Alternative on Resources
- 3. Final Design
- 4. Construction





### **NHDOT Grant Requirements**

- NHDOT Reimburses City for 80% of Funds Expended
- **NHDOT Grant Summary** 
  - \$640,000 Total Grant
  - NHDOT Funding \$512,000
  - \$128,000 City Funding
- **Engineering Study** 
  - **Total Cost NHDOT Funding City Funding**

~\$88,000 ~\$70,400 ~\$17,600 **Remaining Grant Funds** \$552,000 \$441,600 \$110,400





### NHDOT Grant Requirements

- Project Must Come to a Finish Point
  - 1. Engineer Study Concludes No Viable Project "No-Build"
  - 2. Preliminary Design Concludes No Viable Project "No-Build"
  - 3. Project is Constructed

 If Project Does Not "Finish", NHDOT Will Take Back Money Reimbursed





#### If "No-Build" Alternative is Selected

- Complete Engineering Study
- Submit to NHDOT
- Project Finishes

 Total Funds Expended ~\$17,600 City Funds Expended

~\$88,000





#### If "New Trestle" Alternative is Selected

- Complete Engineering Study
- Submit to NHDOT
- Prepare Scope of Work for Preliminary Design
- Submit to City and NHDOT
- Establish Budget for Preliminary Design Effort
  - Estimated at \$200,000





#### If "New Trestle" Alternative is Selected

- Tasks for Preliminary Design
  - Design Charrettes
  - Design Alternatives
  - Historic Consultation
  - Renderings and Preliminary Drawings
  - Updated Costs
  - Public Input
  - Develops Refined Preferred Alternative





#### If "New Trestle" Alternative is Selected

- Secure Additional Funding
  - Roughly \$4 Million Additional Funds Needed
  - Almost All Potential Grants Require City Matching Funds
  - % of City Funding Varies By Grant (Assume 20%)
  - Should Plan on <u>At Least</u> \$800,000 of Additional City Funds
  - Could Take 1 -2 Years to Secure Funding





If "New Trestle" Alternative is Confirmed At End of Preliminary Design

- Complete Preliminary Design
- Submit to NHDOT
- Prepare Final Construction Documents
- Advertise Project
- Construct Project





If "No-Build" Alternative is Selected at Conclusion of Preliminary Design

- Complete Preliminary Design
- Submit to NHDOT
- Project Finishes

Total Funds ExpendedCity Funds Expended

~\$200,000 ~\$40,000 + \$88,000 + \$17,600





City Needs To Determine If Project Should Continue to Preliminary Design

- Yes
  - MJ will Finalize Engineering Study and Prepare Scope and Fee for Preliminary Design
  - Present to City for Approval
- No
  - MJ Will Finalize Engineering Study
  - Project Ends











# NHDOT Letter Dated August 15, 2023

- City Needs to Make a Decision to Move the Project Forward or Cancel the Project by December 2023
  - City Needs to Commit to 20% Match of Additional Funding from NHDOT
  - City Needs to Commit to 100% of Funds Beyond What NHDOT Can Provide
- Commitments Need to be in Writing





#### Questions







## Contact Information

Seth Creighton, AICP City Planning & Zoning Director <u>screighton@franklinnh.org</u> 603-934-2341

Brian Colburn, PE McFarland Johnson Project Manager <u>bcolburn@mjinc.com</u> 603-225-2978









